

KIWANIS BASEBALL FIELD  
CLUBHOUSE RENOVATION  
TOWNSHIP OF GLOUCESTER  
CAMDEN COUNTY  
NEW JERSEY

Clubhouse Renovations

CLARIFICATION NUMBER 1  
CLARIFICATION DATE: November 13, 2012

---

TO ALL PLAN HOLDERS AND PROSPECTIVE BIDDERS:

**THE BID DEADLINE HAS BEEN EXTENDED:**

**NEW BID DATE:** Wednesday, November 21, 2012 at 10:00 A.M., Prevailing Time. The Completion Date for the project has not changed and shall remain March 1, 2013

All bids are being accepted at the Clerk's Office at the Municipal Building on or before the Bid Deadline.

The following clarifications, additions, and deletions are made

SHEET E-1 NEW LIGHTS, CEILING GRID, AND TILES

Replace existing ceiling tile and grid (approximately 800 square feet) as shown on SK-1 (see attached) with new 15/16" white grid and vinyl faced lay-in ceiling tiles. Also replace (8) existing fluorescent fixtures with new 2 x 4 lay-in fluorescent fixtures with prismatic lenses.

SHEET A-1.0 GROUND FLOOR PLAN

Provide a new 2'-10" hollow metal frame and door at existing opening as shown on SK-1.

This clarification supplements and amends the original drawings and specifications, and shall be considered fully as part of the contract documents. The information contained herein shall be used by the Bidder for preparation of the proposal. Bidders must acknowledge receipt of this clarification as set forth in the Bid Documents. Conflicting information is superceded.

---

END OF CLARIFICATION

ACKNOWLEDGED BY:

---

NAME

COMPANY

---

DATE



